

AD-A105 283


HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE
NATIONAL DAM SAFETY PROGRAM. SWISS LAKE ESTATES
JUN 79 R S DECKER, G JAMISON, G ULMER

F/G 13/13
DAM (NO 30109) --ETC(U)
DACW43-79-C-0046

NL

UNCLASSIFIED

1 OF 1
AD &
104-283



END
DATE
FILMED
10-81
DTIC

LEVEL II



OSAGE-GASCONADE BASIN

AD A105283

SWISS LAKE ESTATES DAM

GASCONADE COUNTY, MISSOURI

MO. 30109

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

DTIC FILE COPY



United States Army
Corps of Engineers
... Serving the Army
... Serving the Nation

St. Louis District

DTIC
ELECTE
S OCT 9 1981 D

D

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

JUNE, 1979

81 10 7 090

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Swiss Lake Estates Dam (MO 30109) Gasconade County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Hoskins-Western-Sonderegger, Inc.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-79-C-0046
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE / June 1979 /
		13. NUMBER OF PAGES Approximately 55
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) National Dam Safety Program, Swiss Lake Estates Dam (MO 30109), Osage - Gasconade Basin, Gasconade County, Missouri. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

394 121

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

RESPONSIBILITY. The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

CLASSIFICATION. Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

COMPLETION GUIDE

General. Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

Block 1. Report Number. Enter the unique alphanumeric report number shown on the cover.

Block 2. Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

Block 3. Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

Block 4. Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

Block 5. Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

Block 6. Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

Block 7. Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

Block 8. Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

Block 9. Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

Block 10. Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

Block 11. Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

Block 12. Report Date. Enter here the day, month, and year or month and year as shown on the cover.

Block 13. Number of Pages. Enter the total number of pages.

Block 14. Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

Blocks 15 & 15a. Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

Block 16. Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 17. Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 18. Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

Block 19. Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

Block 20. Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.

SWISS LAKE ESTATES DAM
GASCONADE COUNTY, MISSOURI
MO. 30109

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY
HOSKINS-WESTERN-SONDEREGGER, INC.
CONSULTING ENGINEERS
LINCOLN, NEBRASKA

UNDER DIRECTION OF
ST. LOUIS DISTRICT, CORPS OF ENGINEERS

FOR
GOVERNOR OF MISSOURI

JUNE, 1979

S DTIC
ELECTE
OCT 9 1981
D

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 TUCKER BOULEVARD, NORTH
ST. LOUIS, MISSOURI 63101

SUBJECT: Swiss Lake Estates Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Swiss Lake Estates Dam.

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- 1) Spillway will not pass 50 percent of the Probable Maximum Flood.
- 2) Overtopping could result in dam failure.
- 3) Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY SIGNED 14 MAR 1980
Chief, Engineering Division Date

APPROVED: SIGNED 14 MAR 1980
Colonel, CE, District Engineer Date

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
	SECTION 1 - PROJECT INFORMATION	
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	3
	SECTION 2 - ENGINEERING DATA	
2.1	Design	5
2.2	Construction	5
2.3	Operation	5
2.4	Evaluation	5
	SECTION 3 - VISUAL INSPECTION	
3.1	Findings	6
3.2	Evaluation	8
	SECTION 4 - OPERATIONAL PROCEDURES	
4.1	Procedures	9
4.2	Maintenance of Dam	9
4.3	Maintenance of Operating Facilities	9
4.4	Description of Any Warning System in Effect	9
4.5	Evaluation	9
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	10
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	12
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	13
7.2	Remedial Measures	13

APPENDIX A - MAPS

Plate A-1	Vicinity Topography
Plate A-2	Location Map

APPENDIX B - PHOTOGRAPHS

Plate B-1	Photo Index	
Plate B-2	Photo No. 2	Upstream Slope From Left Abutment
	Photo No. 3	Looking Upstream In Emergency Spillway
Plate B-3	Photo No. 4	Looking Downstream In Emergency Spillway
	Photo No. 5	Crest And Downstream Slope From Left
Plate B-4	Photo No. 6	Principal Spillway Inlet
	Photo No. 7	Outlet End Of Principal Spillway In Center Of Picture
Plate B-5	Photo No. 8	Looking Upstream Across Lake From Sta. 4 + 00
	Photo No. 9	Downstream Slope From Right Abutment
Plate B-6	Photo No. 10	Outlet End Of Principal Spillway
	Photo No. 11	Outlet End Of Principal Spillway
Plate B-7	Photo No. 12	Overview From Left Side

APPENDIX C - PROJECT PLATES

Plate C-1	SCS - Plan and Profile of Dam, Profile of Spillway
Plate C-2	SCS - Section of Dam at Principal Spillway
Plate C-3	Phase I - Section of Dam at Principal Spillway Profile of Spillway
Plate C-4	Phase I - Dam Profile and Spillway Section
Plates C-5 & C-6	SCS - Earthfill Specifications
Plates C-7 to C-11	Missouri Geological Survey Reports

APPENDIX D - HYDRAULIC AND HYDROLOGIC DATA

Plates D-1 & D-2	Hydrologic Computations
Plate D-3	Principal Spillway Rating Curve
Plate D-4	Emergency Spillway Rating Curve
Plate D-5	Ratio of PMF-Discharge Curves
Plates D-6 to D-17	Computer Input and Output for Ratios of PMF

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam	Swiss Lake Estates Dam
State Located	Missouri
County Located	Gasconade County
Stream	Tributary of Puncheon Creek
Date of Inspection	June 26, 1979

Swiss Lake Estates Dam was inspected by an interdisciplinary team of engineers from Hoskins-Western-Sonderegger, Inc. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.


The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers, and developed with the help of several Federal and State agencies, professional engineering organizations and private engineers. Based on these guidelines, this dam is classified as a small size dam with a high downstream hazard potential. Failure would threaten life and property. The estimated damage zone extends approximately 5 miles downstream of the dam. Within the damage zone are 6 dwellings, an unimproved road and Highway W.

Our inspection and evaluation indicates that the spillway does not meet the criteria set forth in the recommended guidelines for a small dam having a high hazard potential. Considering the volume of water impounded and the number of dwellings downstream of the dam, one-half of the Probable Maximum Flood is the appropriate spillway design flood. The spillways will pass the 100-year flood (flood having a one percent chance of being exceeded in any year) without overtopping the dam. The spillways will pass 20% of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

No design data were available for this dam. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These analyses should be obtained in the future.

Other deficiencies observed during the inspection include a few small trees and brush growing along the water edge, a few small trees growing on the downstream slope and in the entrance to the emergency spillway, and growth of trees in the downstream channel.


This dam is reasonably well maintained. However, a program of regular maintenance should be initiated to remove and control the growth of trees and brush on the dam and in the spillway and channel and to assure unobstructed flow into the principal spillway.




Rey S. Decker
E-3703



Gordon Jamison



Garold Ulmer
E-4777



Harold P. Hoskins
Chairman of Board
Hoskins-Western-Sonderegger, Inc.
E-8696



PHOTO NO. 1 - OVERVIEW

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
SWISS LAKE ESTATES DAM - MO 30109
GASCONADE COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of Swiss Lake Estates Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams", dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances.
 - (1) The dam is an earth fill about 730 feet in length and about 37 feet in height located in rolling hills of moderate relief with narrow minature valleys cut into limestone.
 - (2) The principal spillway consists of a 22 inch diameter steel pipe with a 4 X 4 foot weir drop inlet, antivortex plate and conical trash guard. The inlet end of the pipe is hooded and the pipe passes through the embankment.
 - (3) A vegetated earth emergency spillway is cut through cherty clay and the underlying limey shale on the left abutment.

(4) Pertinent physical data are given in paragraph 1.3 below.

- b. Location. The dam is located in the north central portion of Gasconade County, Missouri, as shown on Plate A-2. The dam is shown on Plate A-1 in the NE $\frac{1}{4}$ of Section 28, T44N, R5W. The lake formed behind the dam is shown in the NE $\frac{1}{4}$ of Section 28, T44N, R5W, and the SE $\frac{1}{4}$ of Section 21, T44N, R5W.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Based on these criteria, this dam and impoundment is in the small size category.
- d. Hazard Classification. Guidelines for determining hazard classification are presented in the same guidelines as referenced in paragraph 1.1c above. Based on referenced guidelines, this dam is in the High Hazard Classification. The estimated damage zone extends some 4 to 5 miles downstream, and includes two dwellings and an unimproved road before the stream enters a larger drainage way some 2 miles downstream from the dam. There are 4 dwellings and Highway W located along the larger drainage way between the confluence of the Boggs Creek with the larger creek and its confluence with Puncheon Creek about 4.5 miles below the dam.
- e. Ownership. The dam is owned by Swiss Lake Estates, c/o R. O. Boggs, Box 257, Hermann, MO. 68041.
- f. Purpose of Dam. The dam impounds a recreational lake covering some 40 acres and containing about 520 acre-feet of water.
- g. Design and Construction History. The dam was constructed in 1967. Geologic investigations of the site were made by the Missouri Geological Survey and others (SCS and/or Browning Testing Laboratories, Fulton, MO). Design and construction plans for the dam were prepared by the Soil Conservation Service (SCS), Columbia, MO. Copies of the Missouri Geologic Survey Report and SCS plans are included with this report as Appendix C.
- h. Normal Operating Procedure. There are no operating facilities for this dam. The reservoir level is controlled by rainfall, evaporation and the capacity of the spillways. It was reported by Mr. R.O. Boggs that the emergency spillway has never operated.

1.3 PERTINENT DATA

- a. Drainage Area. 649 acres (1.014 square miles).
- b. Discharge at Damsite.
 - (1) All discharges at the damsite are through a principal spillway consisting of a 4' X 4' steel riser connected with a 22 inch diameter smooth iron pipe outlet and a grassed earth channel ungated emergency spillway.
 - (2) Estimated maximum flood at damsite -- unknown.
 - (3) The principal spillway capacity varies from 0 cfs at elevation 773.0 feet to 66 cfs at the crest of the emergency spillway (elevation 776.0 feet) to 68 cfs at the minimum top of dam (elevation 778.0 feet).
 - (4) The emergency spillway capacity varies from 0 cfs at its crest elevation 776.0 feet to 360 cfs at elevation 778.0 feet (minimum top of dam).
 - (5) Total spillway capacity at the minimum top of dam is 428 cfs \pm .
- c. Elevations (feet above MSL).
 - (1) Top of dam - 778 \pm
 - (2) Principal spillway crest - 773 \pm
 - (3) Emergency spillway crest - 776 \pm
 - (4) Streambed at centerline - 739 \pm
 - (5) Maximum tailwater - unknown
- d. Reservoir. Length (feet) of maximum pool - 2500 \pm
- e. Storage (Acre-feet).
 - (1) Top of dam - 747 \pm
 - (2) Principal spillway crest - 520 \pm
- f. Reservoir Surface (Acres).
 - (1) Top of dam - 49 \pm
 - (2) Principal spillway crest - 40 \pm

g. Dam.

- (1) Type - earth fill
- (2) Length - 730 ft. \pm
- (3) Height - 37 ft. \pm (measured)
- (4) Top width - 15 ft. \pm (measured)
- (5) Side slopes
 - (a) Downstream 2.5H on 1V w/10' berm (plans); 2.4H on 1V with 2.9H on 1V below berm (measured)
 - (b) Upstream - 2.5H on 1V w/8' berm (plans) 2.8H on 1V (measured)
- (6) Zoning - plans show selective placement of most impervious material in center section and least impervious materials in the outside sections.
- (7) Impervious core - as above
- (8) Cutoff - a core trench was excavated to sound bed-rock up to the permanent pool elevation on the abutments.
- (9) Grout curtain - none
- (10) Wave protection - 8 foot sacrificial berm, no riprap
- (11) Internal drainage - unknown

h. Diversion Channel and Regulating Tunnel. None

i. Spillway.

- (1) Principal
 - (a) Type - hooded inlet, 22 inch diameter steel pipe with 4 x 4 ft. steel drop box inlet
 - (b) Crest (invert) elevation - 771 ft. \pm = el. 98.0 on plans
Outlet - 737.4 ft. (plans); 742.8 ft. \pm (measured)
 - (c) Length - 142 ft. \pm
- (2) Emergency
 - (a) Type - vegetated earth on left abutment. Bottom width = 45 ft. \pm
 - (b) Control section - 45 ft. \pm bottom, trapezoidal section with 2H on 1V side slopes
 - (c) Crest elevation - 776 ft. = 103 ft. on plans
 - (d) Upstream Channel - 3% \pm slope. Sparsely vegetated.
 - (e) Downstream Channel - open and clear, well vegetated, slope = 2.5% \pm

j. Regulating Outlets. None

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

Design data available for this dam are included as Appendix C.

2.2 CONSTRUCTION

No construction data were available. It was reported by Mr. R. O. Boggs that the dam was constructed in accordance with SCS specifications.

2.3 OPERATION

No data were available on spillway operation. It was reported by Mr. R. O. Boggs that the emergency spillway has never operated.

- a. Availability. The owner willingly supplied all data that were available.
- b. Adequacy. The available data, field surveys and visual observation presented herein are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. The data are considered to be valid. Information supplied by the owner, Mr. R. O. Boggs, is considered to be valid.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

- a. General. A visual inspection of the Swiss Estates Lake Dam was made on June 26, 1979. Engineers from Hoskins-Western-Sonderegger, Inc., Lincoln, Nebraska making the inspection were: R.S. Decker, Geotechnical; Gordon Jamison, Hydrology; Garold Ulmer, Civil Engineer. Mr. R. O. Boggs, Owner, was present during the inspection.
- b. Dam.
 1. Geology and Soils (Abutment and Embankment). The report of the Missouri Geological Survey (MGS) described geological conditions at the site. Visual observations confirm the findings in the report. All material for the dam was borrowed from the abutments. (Nothing from the bottom). One high abutment borrow area shows as the cleared area, left of the dam, in Photo No. 1. One sample of borrow for the dam was tested by the MGS and produced LL = 37, PI = 20 with maximum standard density (ASTM D 698) of 113 pcf at opt. moisture of 18%. Borings on the dam showed CL or CH materials (based on field classification) to a depth of 2 feet.
 2. Upstream Slope. The upstream slope is well vegetated with a few small trees and brush growing along the water edge. No significant erosion was noted on the face. No indication of slides, slumps or rodent activity was noted.
 3. Crest. The roadway across the crest is well graveled with cherty limestone. The remainder of the crest is well vegetated. No pot holes, slides or slumps were noted along the crest. A few drying cracks were observed which would be expected from the plastic materials used to construct the dam. Measurements on the crest indicate that the dam was constructed essentially as shown on the plans with the constructed top elevation 1 to 1.5 feet higher than the settled elevation (104' = 777') shown. This planned 5% settlement apparently has not occurred to date.
 4. Downstream Slope. The downstream slope is well vegetated with adapted grasses and no erosion was noted. A few small cedar trees are growing on the slope. No cracks, slides, slumps or other deformations were observed on the slope or at the toe. There was no indication of emer-

gence of the phreatic line on the slope nor any sign of seepage along the toe of the dam. There is some water loving grass 20 to 30 feet below the toe on the right side of the spillway scour hole, but it is from surface drainage from the right abutment.

5. Miscellaneous. The vegetative cover and plastic nature of materials in the dam indicate that this dam would withstand considerable overtopping without serious damage.

c. Appurtenant Structures.

- (1) The principal spillway. No deterioration of the pipe spillway was noted. The reservoir level was just below the inlet elevation of the weir at the time of inspection. Rough measurements made during the inspection indicate that the outlet elevation of the pipe is about 5+ feet higher than shown on the plans. This does not affect the operation of the spillway but increases the outlet drop into the scour hole. The protective screen over the inlet is in poor condition.
- (2) The emergency spillway is well vegetated with no indications of erosion slides or slumps. A few small trees are growing in the entrance. Discharge from the emergency spillway should not endanger the integrity of the dam. Measurements on the spillway indicate that the crest elevation of 776' is one foot higher than the planned elevation of 775' (102' on plans). This should not adversely affect the planned function and operation of the spillway. It should be beneficial since it increases the flood storage, reduces the incidence of spillway operation, and still maintains the planned 2 feet of freeboard on the dam.
- (3) Drawdown Facilities. There are no drawdown facilities for this dam.

d. Reservoir Area. No significant erosion was noted around the shoreline of the reservoir.

- e. Downstream Channel. The scour hole at the outlet of the pipe spillway has eroded (or was originally excavated) to depth of about 5 feet below the pipe. It is well armored with limestone cobble and large gravel and appears to be stable. The downstream channel is pretty well overgrown with trees but appeared capable of carrying principal spillway discharges. The channel appeared to be stable.

3.2 EVALUATION

This structure appears to be in good condition with no serious potential of failure. The discrepancies in measured and planned elevations of the emergency spillway, top of dam and principal spillway outlet should not adversely affect the safety of the dam. None of the deficiencies noted (few trees on slopes and in the entrance to the emergency spillway, lack of an adequate trash rack on the principal spillway, and lack of seepage and stability analyses) indicate a need for any immediate remedial action.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

There are no controlled outlet works for this dam. The pool level is controlled by rainfall, evaporation, and the capacity of the uncontrolled spillways.

4.2 MAINTENANCE OF DAM

The dam is reasonably well maintained. Action should be taken to correct the minor deficiencies noted in Sections 3 and 7.2.

4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

4.5 EVALUATION

There does not appear to be any serious potential of failure of this structure.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

- a. Design Data. Detailed plans for the structure were furnished by the owner. The field inspection and survey indicate that both the emergency spillway crest and the top of the dam are 1 foot higher than per the original plans. Both the owner's plans and the plan, profiles, and cross-sections obtained from the field survey are attached in Appendix C.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the owner's plans and the USGS Swiss, Missouri 7 1/2 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection.
- c. Visual Observations.
 - (1) The principal spillway appeared to be in good condition except for the protective screen on the inlet.
 - (2) The channel downstream of the principal spillway outlet is fairly well clogged with trees and brush.
 - (3) The emergency spillway is located in the left abutment of the dam. A few small trees are located at the entrance to the spillway. Spillway release should not endanger the integrity of the dam, since it outlets on the natural slope some distance downstream from the structure.
 - (4) No drawdown facilities are available to evacuate the pool.
- d. Overtopping Potential. The spillways are too small to pass 50% of the probable maximum flood without overtopping. The spillways will pass 20% of the PMF without overtopping. The 100-year (1 percent) peak outflow discharge is approximately 16% of the spillway capacity. The dam should withstand considerable overtopping without serious damage.

The results of the routings through the dam are tabulated in regards to the following conditions.

<u>Frequency</u>	<u>Inflow Discharge cfs</u>	<u>Outflow Discharge cfs</u>	<u>Maximum Pool Elevation</u>	<u>Freeboard Top of Dam Min. Elev. 778.0</u>	<u>Time Dam Overtopping Hr.</u>
100 Yr.	1600	70	775.9	+2.1	0
1/2 PMF	4500	3900	779.3	-1.3	4+
PMF	8900	7900	780.2	-2.2	6+
0.2 PMF	1800	380	777.8	+0.2	0

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard rating and a small size. Therefore, the 1/2 PMF to the PMF is the test for the adequacy of the dam and its spillway. The estimated damage zone is described in Paragraph 1.2d in this report.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. The dam appears to be structurally stable. Embankment slopes and CL-CH materials in the dam should provide adequate safety against shear failures. Analyses presented in Section 5 indicate that the dam will be overtopped by 1.3 feet of water for a period of 4 hours \pm by one-half the Probable Maximum Flood. It would appear, however, that such an occurrence would not seriously damage the structure.
- b. Design and Construction Data. The design data that were available did not contain slope stability nor seepage analyses which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam. It was reported by Mr. R. O. Boggs that the emergency spillway has not operated.
- d. Post Construction Changes. The inspection team is not aware of any post-construction changes on this dam.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of the magnitude predicted in this area is not expected to cause structural failure of this dam. However, the dam is located in an area that could have been affected by the structural activity of the Pershing-Bay-Gerald anticlinal formations and appropriate earthquake loadings should be included in stability analyses.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

- a. Safety. This dam does not appear to have any serious potential of failure. The dam will impound the flood resulting from the 100 year storm without flow in the emergency spillway. The flood from one-half the Probable Maximum Flood will overtop the dam. The effects of such overtopping are not known but it would appear that it would not seriously impair the safety of the structure. The lack of seepage and stability analyses comparable to the "Recommended Guidelines for Safety Inspection of Dams" is considered to be a deficiency.
- b. Adequacy of Information. The investigational and design data available along with visual observations and performance history are considered adequate to support the conclusions in this report. Seepage and stability analyses comparable to the requirements of the guidelines were not available which is considered a deficiency.
- c. Urgency. The items recommended in paragraph 7.2.a should be pursued on a high priority basis.
- d. Necessity for Phase II. Phase II investigation is not considered necessary.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of this magnitude is not expected to be hazardous to this dam. However, additional studies should be performed to assess the actual seismic potential in the specific area. The lack of seismic stability analysis is considered a deficiency.



7.2 REMEDIAL MEASURES

- a. Alternatives. Additional information should be obtained to determine the increase in the height of dam or the size of the spillway that is necessary to pass one half the Probable Maximum Flood without overtopping the dam. The services of an engineer experienced in the design and construction of dams should be obtained to evaluate the overtopping potential and resultant effects, to provide seepage and stability analyses, including earthquake loads, of the present dam, and to design protective measures, if required.


b. O & M Maintenance and Procedures

- (1) The trees and shrubs should be removed from the embankment slopes and from the inlet of the emergency spillway, and the trash rack (screen) on the principal spillway should be rehabilitated. A program of regular inspection and maintenance should be initiated to prevent their recurrence.

APPENDIX A
MAPS



VICINITY TOPOGRAPHY
 SWISS LAKE ESTATES DAM
 GASCONADE COUNTY, MO.
 MO. 30109
PLATE A-1



APPENDIX B
PHOTOGRAPHS




PHOTO INDEX

SWISS LAKE ESTATES DAM

GASCONADE COUNTY, MISSOURI

MO. 30109

PLATE B-1



PHOTO NO. 2 - UPSTREAM SLOPE FROM LEFT ABUTMENT



PHOTO NO. 3 - LOOKING UPSTREAM IN EMERGENCY SPILLWAY



PHOTO NO. 4 - LOOKING DOWNSTREAM IN EMERGENCY SPILLWAY



PHOTO NO. 5 - CREST AND DOWNSTREAM SLOPE FROM LEFT



PHOTO NO. 6 - PRINCIPAL SPILLWAY INLET



PHOTO NO. 7 - OUTLET END OF PRINCIPAL SPILLWAY IN CENTER
OF PICTURE



PHOTO NO. 8 - LOOKING UPSTREAM ACROSS LAKE FROM STA. 4 + 00



PHOTO NO. 9 - DOWNSTREAM SLOPE FROM RIGHT ABUTMENT



PHOTO NO. 10 -
OUTLET END OF PRINCIPAL
SPILLWAY




PHOTO NO. 11 - OUTLET END OF PRINCIPAL SPILLWAY



PHOTO NO. 12 - OVERVIEW FROM LEFT SIDE

APPENDIX C
PROJECT PLATES






PLATE C-1




CROSS-SECTION AT STA. 2+62

Scale: 1" = 20' H. & V.




PROFILE OF SPILLWAY

Scale: 1" = 20' H.
1" = 10' V.



PROFILE ALONG CENTERLINE OF DAM

Scale: $1'' = 100' H$
 $1'' = 5' V$



SPILLWAY SECTION (E OF DAM)

Scale: $1'' = 20' H$
 $1'' = 5' V$

February 12, 1963

UNITED STATES DEPARTMENT OF AGRICULTURE
Soil Conservation Service
Columbia, Missouri

EARTH FILL SPECIFICATIONS FOR PL-46 WORK

A. PURPOSE

The following specifications for earth fills are to be used as minimum requirements in building earth fills for farm ponds, grade stabilization structures, floodwater retarding structures, etc. Parts of the specifications are also applicable in the building of dikes and levees.

B. PREPARATION OF FILL SITE AND BORROW AREA

1. All trees, stumps, trash, brush, sod, large roots, perishable material and loose soil shall be removed from the site.
2. Topsoil material shall be stripped from the foundation and borrow areas and deposited in storage piles.
3. After the stripping operation, the ground surface within the foundation area shall be roughened by scarifying or plowing to provide a bond between the foundation and earth fill.
4. Overhanging banks, pits, and holes within the foundation area shall be graded to 1:1 slope or flatter to provide bond with the fill.
5. Springs encountered in preparing the site shall be properly drained or sealed.

C. CORE TRENCH CONSTRUCTION

1. The core trench shall be excavated to the extent and dimensions shown on the plans or directed by the SCS technician. The side slopes of the core trench shall be 1:1 or flatter.
2. The core trench shall be backfilled with the most impervious material available at the site. Moisture content of the backfill material shall be sufficient to secure proper compaction. (When kneaded in the hand the soil should just form a ball which does not readily separate to meet the requirements for adequate moisture content.)

D. PIPES FOR PRINCIPAL SPILLWAY AND STOCK WATER

1. Pipes and appurtenances for the pipe spillway and stock watering system shall be placed according to the plans as directed by the SCS technician. The pipes shall be placed on solid foundations either (1) in trenches excavated in undisturbed soil or (2) on fill material placed in 6-inch layers and properly compacted with equipment. Anti-seep collars shall be installed on both stockwater pipe and one conduit pipe as planned or as

directed by the SCS technician. Where no cradle is provided under the spillway pipe, the foundation shall be shaped (circular) to fit the pipe for a depth equal to $1/4$ the diameter of the pipe. Anti-swirl walls or baffles shall be installed as called for on the plans or as directed by the SCS technician.

E. CONSTRUCTION OF FILL

1. Earth fill material shall not contain any appreciable concentration of vegetation, roots, large rocks, frozen soil, or other foreign substances. Moisture content shall be sufficient to secure proper compaction. (When kneaded in the hand, the soil should just form a ball which does not readily separate to meet the requirements for adequate moisture content.)
2. The fill material shall be placed in approximately 6-inch layers that extend over the full width and length of the dam. Each layer shall be compacted by the operation of tractors, earth moving equipment, or rollers. If the moisture content of the fill material is deficient, water shall be sprinkled on the surface of each lift of the fill material and thoroughly mixed then compacted prior to placing additional fill. If moisture content of the fill material is excessive, the fill material shall not be used or shall be air dried to proper moisture content before placement.
3. Backfill adjacent to the pipe spillway and stock watering system shall be placed in 6-inch layers and tamped by hand or with mechanical tampers. Rubber-tired tractors may be used to supplement the tamping along the sides of the pipe. Backfill shall be brought up approximately equal on each side of the pipe so as to prevent side movement of the pipe. Heavy equipment shall not be driven over the pipes until a minimum of 2 feet of compacted fill has been placed over the top of the pipe.
4. Frozen material shall not be placed in a fill nor shall fill material be placed on frozen earth. When fill material starts to freeze during placement, fill construction shall be stopped until proper temperatures prevail. When it is desired to place fill on an area that is frozen, the frozen soil shall be permitted to thaw completely and dry to the proper moisture content before placement, or the frozen material shall be removed completely before placing additional fill.
5. At sites where there is a limited amount of the most impervious fill material, (1) this material shall be placed in the core trench and the center section of the embankment and (2) the least impervious material shall be placed in the downstream part of the embankment.
6. The topsoil material saved in the site preparation shall be placed as a top dressing on the surface of the earth fill and side spillway. It shall be evenly spread to a thickness as shown on the plans or directed by the SCS technician.
7. The finished grade of the earth fill and side spillway shall be to the dimensions and side slopes shown on the plans.

ENGINEERING GEOLOGY OF THE R. O. BOGGS LAKE SITE, GASCONADE COUNTY

The proposed lake site for R. O. Boggs located in the NW $\frac{1}{4}$ NW $\frac{1}{4}$ sec. 28, T.44 N., R.5 W., Gasconade County (Hermann Quad.) was examined and found to be a poor risk geologically. Surficial investigation of the geological conditions revealed the following.

1. The right valley slopes are fairly gentle and apparently covered with a fairly thick soil cover, 10 - 20 feet. Whereas the left (south) valley slopes are much steeper and have numerous isolated rock outcrops along the bluff for approximately 500 yards upstream from the proposed centerline. However, beyond this both valley slopes are fairly gentle.
2. The bedrock at this site is thin bedded Jefferson City Dolomite. These bedding planes are generally less than 1 foot apart and the majority appear to be loosely bedded. This condition will allow for considerable water loss.
3. Numerous vertical joints are also present from hairline to an inch or more in width.
4. There is a zone of solution channels approximately 6 feet above the stream bed at the vicinity of the proposed centerline. This zone can be traced about 200 yards upstream. At this point the zone is either covered by soil or is at creek level. Although these solution channels appear to be filled with clay at the surface large volumes of water could be lost.
5. Springs were reported above the dam by SCS field men as flowing in the fall with water disappearing into the ground before reaching the proposed centerline. The water was either entering the alluvium but more probably a fracture in the rock.

This site can not be considered as a good risk at this time. However, should the owner wish to verify that the same geologic conditions do or do not occur underground as noticed and reported as existing then the following steps are recommended prior to future design.

1. Drill several (3 to 5) core holes on the left abutment from proposed centerline to approximately 500 yards upstream and 2 or more in the valley floor at centerline. These holes should be diamond cored in order to allow a geologist to examine bedding plane characteristics and detect presence of voids. The exact number of holes will be, of necessity, determined by what is found by the geologist. If possible to get the drill at desired surface elevation each hole will be about 40 feet deep.
2. Pressure test at least 3 of the borings to determine how much water loss, if any, will result.
3. Drill approximately 20 feet into bedrock plus pressure testing in the floor of the valley to determine water loss in this manner.
4. Check with drill or back hoe to see if water is moving through the alluvium as field evidence exists that the creek was forced to the left wall by man.

Should the above program indicate that a dam can be built at the desired location economically then the following suggestions are offered.

1. Obtain borrow from the right side of the valley, preferably above the waterline.
2. Cut the abutment core trench quite deep into the rock. It may be necessary to cut the core trench a few feet into rock in the valley floor. The Jefferson City when thin bedded is rippable on loose bedding planes with a back mounted ripper.
3. Cover most of the outcrops especially the solution channel zone with grout or clay.

The lack of a heavy soil cover on the left valley wall in the vicinity of the proposed centerline makes completely sealing seepage areas quite expensive. The drilling program may not expose all hazards and extreme care must be utilized in interpreting the data. Even with the boring investigation and utilizing all economical remedial methods the lake, if built, will in all probability leak.

A geologist from the Missouri Geological Survey will be able to assist in the drilling program if so desired.

Edwin E. Lutzen

Edwin E. Lutzen
Engineering Geologist
Missouri Geological Survey
February 7, 1967

Note: This site not used.

ADDENDUM TO THE BOGGS LAKE SITE, GASCONADE COUNTY

Subsurface exploration has shown that both sites are suitable geologically and recommended for construction. Only two particular items of importance were noted. One item on the downstream lake site is that the bedrock surface should be ripped with heavy duty back mounted rippers on large caterpillars so that seepage through the weathered surface rock cannot occur. The other item is at the upstream site where the wet soupy silt under the dam foundation in one section of the stream channel should be removed so that all of the dam can be founded on firm material. This will require over excavation more than necessary for the core trench.

*** Downstream Site** - Subsurface exploration borings of the downstream site on the steep left abutment, and two holes in the valley floor show that the bedrock is firm, fresh and tight. Pressure testing showed no water loss. Therefore no hazards are expected to occur to the lake from the bedrock aspect other than possible seepage through weathered zones of the surface bedrock exposed on the steep hillslope on the left side of the valley and on the gently sloping right valley slope.

The drilling exploration showed that near the stream channel 12 to 15 feet of alluvial gravels cover the underlying bedrock. The bedrock is weathered for a depth of 2 to 3 feet so that firm bedrock was not encountered until about 18 feet in depth. It is recommended that the core trench be deepened to fresh bedrock even in the deeper portion of the stream channel. This is a relatively narrow sector and the bedrock profile seems to be a uniform "U" shaped profile that drops from the steep left abutment slope and rises somewhat more gently to the right valley slope. On the right slope soil cover is only about 7 feet in thickness so that the problems of excavating to bedrock will be much less on this slope. Except for the recommendation that the core trench be excavated to bedrock across the entire valley floor and that weathered bedrock be removed by excavation so that the dam can be seated into firm fresh material no other unusual features were noted at this site.

The drains on the downstream dam should be considered if a lagoon is to be constructed there. Even with an "impervious" clay core there is a certain amount of water passage through the dam. This seepage will be of sufficient amount to weaken the backslope of a lagoon and with time could be a serious detriment to the lagoon. Sand and gravel filled or perforated pipe leading away from the lagoon will prevent this.


**** Upstream Site** - Subsurface exploration of the upstream site indicates that the foundation material consists of water saturated silts, sands and clays especially near the stream channel on the right portion of the valley. Much of this material consists of soupy silt and water saturated gravels. It has insufficient bearing strength even for the foundation of the dam upstream of the core. Depths to bedrock across the valley floor averaged 13 feet becoming somewhat less toward the left side of the valley where it is only 9 feet. Bedrock was encountered at about 7 feet with about 3 feet of weathered bedrock on the left valley slope. Depth to bedrock on the right valley slope is 17 feet due to a terrace. This is the terrace on which the barn and house are situated. The terrace material consists of yellow silty clay (CL) with boulder and gravel layers. While this

**** Site used**
*** Site not used**

excavation will be somewhat deep on the lower portion of the terrace it is nevertheless recommended that the core trench of the dam be cut to bedrock across the entire valley floor and on the abutments. Seepage by lateral water movement through the terrace could be high due to possible stratified layers of sands or gravels. It would be much cheaper to excavate a cutoff core trench through the terrace than repair seepage at a later date by grouting.

Because of the unstable material that is associated with the spring upstream of the dam site, a relatively large amount of excavation will be required under part of the dam foundation in the floodplain. In order to reduce the amount of excavation, it is suggested that the core trench at the centerline of the dam be placed near or in the stream channel as it cuts across the valley so that the core trench can be somewhere near the right bank of the stream channel. This would perhaps reduce the amount of overexcavation needed under the dam upstream of the core trench. Where material in the dam foundation consists of the unstable wet silts and gravels it must be removed. The amount of this material cannot be judged at present without an extensive amount of subsurface boring. Even then it would be somewhat difficult to estimate the yardage accurately. Therefore close examination of the foundation must be maintained during the construction of the dam so that it can be assured that all unstable material is removed from the foundation.

Due to the high water content within the soils at this site, it will probably be necessary to excavate with a drag line. However, if the flow through the soils is spotty as indicated by surface spring, the excavation can be made with mobile equipment provided that adequate pumps are available. The slopes of the trench will have to be much flatter than in a dry operation since the water bearing soils will have a tendency to slide. For safety it is recommended that the backslopes be cut on $3\frac{1}{2}$ on 1 or flatter.



James H. Williams
Chief, Eng. Geol. Section
Missouri Geological Survey
June 12, 1967

SOILS DATA BOGGS LAKE SITE, GASCONADE COUNTY

Sample No. 1 taken from Borrow Site - Downstream Dam*

The Atterbergs consisting of the plastic limit, liquid limit, and shrinkage limit were determined on this sample. The liquid limit using the one point method is 40%, the plastic limit is 16% with a plastic index of 24, the shrinkage limit is 14% of the volume, therefore this test puts this material in the lean clay (CL). Using the standard proctor of 1/30th cubic foot mold with a 5 lb. hammer three lifts, maximum density is then determined to be 108 lb. per cubic foot dry at 18% moisture.


Sample No. 2 taken from Borrow Site - Upstream Dam**

In tests on sample No. 2, the liquid limit was determined to be 37%, the plastic limit was 17% with a shrinkage limit of 13% of the volume, the plastic index is therefore 20. The maximum dry density as determined on the standard proctor was 113 lb. per cubic foot at 18% moisture. The curve on this one indicates that it blow beyond maximum density quite rapidly on the wet side.

From the testing of these two samples it is apparent or evident that if this material is used as a borrow for the dam that it will be quite satisfactory. However, the compaction with a sheeps foot or rubber tired roller should be maintained throughout the project. The compaction should be in 95% or better of the standard and the moisture content should not vary from 18% moisture, that can be approximately 2% on the dry side. Due to the behavior of the soils in the laboratory, it is not recommended that the soil be compacted too wet. The material will have a tendency to shrink and crack and could cause problems in this manner prior to the filling of the dam. However, when placed on the slightly dry side or at optimum, the soil will maintain its equilibrium until the lake is full and the phreatic line has been established.

* Site not used

** Site used



Edwin E. Lutzen
Engineering Geologist
Missouri Geological Survey
June 13, 1967

APPENDIX D
HYDRAULIC AND HYDROLOGIC DATA

HYDROLOGIC COMPUTATIONS

1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs.
 - a. Twenty-four hour, 100-year rainfall for the dam location were taken from the data for the rainfall station at Sullivan, MO. as supplied by the St. Louis District, Corps of Engineers per their letter dated 6 March 1979. The twenty-four hour probable maximum precipitation was taken from the curves of the Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis policy and guidance for hydraulics and hydrology.
 - b. Drainage area = 1.014 square miles (649 acres).
 - c. Time of concentration of runoff = 34 minutes (computed from Kirpich formula).
 - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the 100-year precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the crest of the principal spillway riser.
 - e. The total twenty-four hour storm duration losses for the 100-year storm were 3.84 inches. The total losses for the PMF storm were 2.50 inches. These data are based on SCS runoff curve No. 82 and No. 66 for antecedent moisture conditions SCS AMC III and AMC II respectively. The watershed is composed of primarily SCS soil groups B and C and consists of mostly wooded areas with approximately 20% in pasture.
 - f. Average soil loss rates = 0.10 inch per hour approximately (for PMF storm, AMC III).
2. The combined discharge rating consisted of three components: the flow through the principal spillway, the flow through the emergency spillway and the flow going over the top of the dam.

- a. The principal spillway rating was developed by using the weir and full conduit flow equations.


(1) Weir Flow equation ($Q = CLH^{1.5}$)
where C = weir coefficient = 3.1
L = effective weir length, ft. = 16
H = total head, ft.


(2) Full conduit flow equation


$$Q = a \sqrt{\frac{2gH}{1 + K_e + K_b + K_p L}}$$

where a = cross-sectional area of pipe, $\text{ft}^2 = 2.64$
H = total head, ft.
 K_e = coefficient for entrance loss = 0.5
 K_b = coefficient for bend loss = 0.034
 K_p = coefficient for pipe friction loss = 0.0119
L = length of pipe, ft. = 148

- b. The emergency spillway ratings were developed using the Corps of Engineers Surface Water Profile HEC-2 computer program.
- c. The flows over the dam were determined using the dam overtopping analysis within the HEC-1 (Dam Safety Version) program.
3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The output and plotted hydrographs are attached.







ROUTED FLOWS INTO 30107 AT SERVERDIR.

CREL	\$PMID	COQM	EXPM	ELEV	COQL	CAMEA	EXPL
773.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

УДН ПАТА

TOPEL	CUQD	EXPQ	OAPWIN
778.0	3.0	1.5	680.

STATION 00002, PLAN 1, RAIL 1

END-OF-CERIGON HYDROGRAPH DRUINFES

[illegible]

SIATION 00002, PLAN 1, RATIO 4

END-OF-PLANT HYDROGRAPH CURVES

[illegible][illegible]

719.	717.	715.	713.	711.	709.
709.	707.	705.	703.	701.	699.
697.	695.	693.	691.	689.	687.
685.	683.	681.	679.	677.	675.
673.	671.	669.	667.	665.	663.
661.	659.	657.	655.	653.	651.
649.	647.	645.	643.	641.	639.
637.	635.	633.	631.	629.	627.
625.	623.	621.	619.	617.	615.
613.	611.	609.	607.	605.	603.
601.	599.	597.	595.	593.	591.
589.	587.	585.	583.	581.	579.
577.	575.	573.	571.	569.	567.
565.	563.	561.	559.	557.	555.
553.	551.	549.	547.	545.	543.
541.	539.	537.	535.	533.	531.
529.	527.	525.	523.	521.	519.
517.	515.	513.	511.	509.	507.
505.	503.	501.	499.	497.	495.
493.	491.	489.	487.	485.	483.
481.	479.	477.	475.	473.	471.
469.	467.	465.	463.	461.	459.
457.	455.	453.	451.	449.	447.
445.	443.	441.	439.	437.	435.
433.	431.	429.	427.	425.	423.
421.	419.	417.	415.	413.	411.
409.	407.	405.	403.	401.	399.
397.	395.	393.	391.	389.	387.
385.	383.	381.	379.	377.	375.
373.	371.	369.	367.	365.	363.
361.	359.	357.	355.	353.	351.
349.	347.	345.	343.	341.	339.
337.	335.	333.	331.	329.	327.
325.	323.	321.	319.	317.	315.
313.	311.	309.	307.	305.	303.
301.	299.	297.	295.	293.	291.
289.	287.	285.	283.	281.	279.
277.	275.	273.	271.	269.	267.
265.	263.	261.	259.	257.	255.
253.	251.	249.	247.	245.	243.
241.	239.	237.	235.	233.	231.
229.	227.	225.	223.	221.	219.
217.	215.	213.	211.	209.	207.
205.	203.	201.	199.	197.	195.
193.	191.	189.	187.	185.	183.
181.	179.	177.	175.	173.	171.
169.	167.	165.	163.	161.	159.
157.	155.	153.	151.	149.	147.
145.	143.	141.	139.	137.	135.
133.	131.	129.	127.	125.	123.
121.	119.	117.	115.	113.	111.
109.	107.	105.	103.	101.	99.
97.	95.	93.	91.	89.	87.
85.	83.	81.	79.	77.	75.
73.	71.	69.	67.	65.	63.
61.	59.	57.	55.	53.	51.
49.	47.	45.	43.	41.	39.
37.	35.	33.	31.	29.	27.
25.	23.	21.	19.	17.	15.
13.	11.	9.	7.	5.	3.
1.	0.	0.	0.	0.	0.

PEAK BOTTOM IS 3983. AT TIME 16.00 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL
CFS	1134.	331.	331.	9941.
CMS	110.	9.	9.	2700.
IPCHES	13.41	12.15	12.15	12.15
MM	264.33	308.56	308.56	308.56
AC-FI	563.	657.	657.	657.
THOUS CU M	694.	810.	810.	810.

91 VI *

STATION 00000002

	500.	1000.	1500.	2000.	2500.	3000.	3500.	4000.	4500.	0.	0.	0.
50												
55												
60												
65												
70												
75												
80												
85												
90												
95												
100												
105												
110												
115												
120												
125												
130												
135												
140												
145												
150												
155												
160												
165												
170												
175												
180												
185												
190												
195												
200												
205												
210												
215												
220												
225												
230												
235												
240												
245												
250												
255												
260												
265												
270												
275												
280												
285												
290												
295												
300												
305												
310												
315												
320												
325												
330												
335												
340												
345												
350												
355												
360												
365												
370												
375												
380												
385												
390												
395												
400												
405												
410												
415												
420												
425												
430												
435												
440												
445												
450												

PLATE D-11

4.45 571
 4.50 591
 4.55 591
 5.00 601
 5.05 611
 5.10 621
 5.15 631
 5.20 641
 5.25 651
 5.30 661
 5.35 671
 5.40 681
 5.45 691
 5.50 701
 5.55 711
 6.00 721
 6.05 731
 6.10 741
 6.15 7501
 6.20 7601
 6.25 7701
 6.30 7801
 6.35 790 1
 6.40 800.1
 6.45 810 1
 6.50 820 1
 6.55 830 1
 7.00 840 1
 7.05 850 1
 7.10 860 1
 7.15 870 1
 7.20 880 1
 7.25 890 1
 7.30 900 1
 7.35 910 1
 7.40 920 1
 7.45 930 1
 7.50 940 1
 7.55 950 1
 8.00 960 1
 8.05 970 1
 8.10 980 1
 8.15 990 1
 8.20 1000 1
 8.25 1010 1
 8.30 1020 1
 8.35 1030 1
 8.40 1040 1
 8.45 1050 1
 8.50 1060 1
 8.55 1070 1
 8.60 1080 1
 8.65 1090 1
 8.70 1100 1
 8.75 1110 1
 8.80 1120 1
 8.85 1130 1
 8.90 1140 1
 8.95 1150 1
 9.00 1160 1
 9.05 1170 1
 9.10 1180 1
 9.15 1190 1

11.55117.0
 11.55120.0
 11.55121.0
 11.55122.0
 11.55123.0
 11.55124.0
 11.55125.0
 11.55126.0
 11.55127.0
 11.55128.0
 11.55129.0
 11.55130.0
 11.55131.0
 11.55132.0
 11.55133.0
 11.55134.0
 11.55135.0
 11.55136.0
 11.55137.0
 11.55138.0
 11.55139.0
 11.55140.0
 11.55141.0
 11.55142.0
 11.55143.0
 11.55144.0
 11.55145.0
 11.55146.0
 11.55147.0
 11.55148.0
 11.55149.0
 11.55150.0
 11.55151.0
 11.55152.0
 11.55153.0
 11.55154.0
 11.55155.0
 11.55156.0
 11.55157.0
 11.55158.0
 11.55159.0
 11.55160.0
 11.55161.0
 11.55162.0
 11.55163.0
 11.55164.0
 11.55165.0
 11.55166.0
 11.55167.0
 11.55168.0
 11.55169.0
 11.55170.0
 11.55171.0
 11.55172.0
 11.55173.0
 11.55174.0
 11.55175.0
 11.55176.0
 11.55177.0
 11.55178.0
 11.55179.0
 11.55180.0

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE FEET (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	RATIOS APPLIED TO FLOWS						
					1	2	3	4	5	6	7
					.10	.20	.35	.50	.65	.80	1.00
HYDROGRAPH AT	00001	1.01	1	891.	1782.	3119.	4456.	5793.	7130.	8912.	
	(2.63)	(25.24)	50.47)	88.33)	126.19)	164.04)	201.90)	252.37)	
PIAUED ID	00002	1.01	1	66.	380.	2366.	3883.	5171.	6466.	7938.	
	(2.63)	(1.87)	10.76)	66.97)	109.95)	146.43)	182.93)	224.79)	

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1													
RATIO OF PF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	SPILLWAY CREST		TOP OF DAM		TIME OF MAX OUTFLOW		TIME OF FAILURE	
						INITIAL VALUE	520.	773.00	773.00	HOURS	HOURS	HOURS	HOURS
			520.	0.			773.00	773.00	778.00				
			0.	0.			0.	0.	747.				
									747.				
RATIO OF PF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS								
.10	775.93	0.00	647.	66.	0.00				18.50	0.00		0.00	
.20	777.82	0.00	738.	380.	0.00				17.15	0.00		0.00	
.30	778.85	0.82	792.	2366.	3.32				16.98	0.00		0.00	
.50	779.27	1.27	811.	3883.	4.17				16.00	0.00		0.00	
.65	779.58	1.58	827.	5171.	5.08				16.00	0.00		0.00	
.80	779.86	1.86	841.	6460.	5.67				16.00	0.00		0.00	
1.00	780.16	2.16	861.	7938.	6.25				16.00	0.00		0.00	

X

